

Repair Improvement and Repainting of the damage Perimeter Fence at the back of the container van east corner of the central bank fence beside DENR site, covered Parking and access road concreting

SCOPE OF WORKS:

A. FOR PERIMETER FENCE

1. Cleaning the area
2. Mobilization/Demobilization of Materials.
3. Demolition of Existing Fence
4. Excavation
5. Construction of footing foundation
6. Construction of concrete column
7. Construction of tie beam/wall footing
8. Setting of chb 6"
9. Fabrication/Installation of Fence cyclone wire (pls. see sketch plan)
10. Fabrication/Installation of column using 6" B.I. pipe trusses using tubular (pls. see sketch plan)
11. Installation of Electrical Wirings and Lightings
12. Plastering works
13. Painting Works
14. Cleaning

B. FOR ACCESS ROAD CONCETING

1. Site Clearing stake out work
2. Scripping and Back Filling of (1.30% compaction)
3. Tampering using roller compactor
4. Gravel bedding
5. Installation of formwork)
6. Installation of Steel Bars
7. Concrete Pouring
8. Cleaning.

C. FOR COVERED PARKING

1. stake out work
2. Tampering using roller compactor
3. Gravel bedding
4. backfilling
5. Installation of formwork)
6. Installation of Steel Bars
7. Concrete pouring of Footing foundation and column (pls see sketch plan)
8. Fabrication/Installation of column using 2" B.I. pipe.(pls see sketch plan)
9. Fabrication of Trusses using tubular (pls. see sketch plan)
10. Roofing Installation pre-painted (rib type)
10. Installation of Electrical Wirings and Lightings
11. Plastering works
12. Painting Works
13. cleaning

SCOPE OF WORKS

C-10 Installation of Electrical Wiring and Lightings

- a. Supply & Delivery of Materials
- b. Installation/Layout of 4 branches Panel Board at Dog House(EE Rm.), Pipes and Fittings(Hangers & Support), Electrical Wire, Suspended Fluorescent Lamp Fitures, Duplex Convenience Outlet, and other Accessories.
- c. Termination, Splicing and Tapping (source is at Dog House/EE rm.)
- d. Clearing/cleaning and restoration of the areas affected by Electrical Works
- e. Testing and commissioning of the whole system

D. For contruction of Electrical manhole and Excavation for Cable Trenching

1. Site clearing / stake out work.
2. Excavation works for cable trenching and electrical manhole.
3. CHB filling for electrical manhole.
4. Plastering works to all hollow blocks.
5. PVC Pipe laying for cable trenching.
6. Laying of Wire mesh
7. Restoring of concrete and asphalt in damage access road cause by trenching.
8. Cleaning the site.